



1307 West Lehigh Street  
Bethlehem, PA 18018  
610-866-9663 Office  
info@keycodes.net  
[www.keycodes.net](http://www.keycodes.net)

## RAMPS (2015 IRC)



**R311.8.1 Maximum slope.** Ramps shall have a maximum slope of 1 unit vertical in 12 units horizontal (8.3 percent slope).

**Exception:** Where it is technically infeasible to comply because of site constraints, ramps may have a maximum slope of one unit vertical in eight horizontal (12.5 percent slope).

**R311.8.2 Landings required.** A minimum 3-foot-by-3-foot landing shall be provided:

1. At the top and bottom of ramps.
2. Where doors open onto ramps.
3. Where ramps change direction.

**R311.8.3 Handrails required.** Handrails shall be provided on at least one side of all ramps exceeding a slope of one unit vertical in 12 units horizontal (8.33-percent slope).

**R311.8.3.1 Height.** Handrail height, measured above the finished surface of the ramp slope, shall be not less than 34 inches and not more than 38 inches

**R311.8.3.2 Grip size.** Handrails on ramps shall comply with Section R311.7.7.3.

**R311.8.3.3 Continuity.** Handrails where required on ramps shall be continuous for the full length of the ramp. Handrail ends shall be returned or shall terminate in newel posts or safety terminals. Handrails adjacent to a wall shall have a space of not less than 1-1/2 inches between the wall and the handrails.